



Brushed Concrete Base Snetterton, Norfolk

Overview

After visiting a returning client at their site in Snetterton, it became clear they desired a new external concrete base to support an outside fridge pack, used for their industrial unit.



Completion Date: July 2023

Scope of Works: Installation of a new concrete base for a commercial client

Project Management Team: Ben Trundle

Project

This project was quite straight-forward in terms of complexity.

The 150m² area was excavated by our team on site, who then installed and compacted a crushed concrete sub base, which was subsequently covered with the poured concrete you can see at finish level.

The area was divided into smaller sections using K Form, and the poured concrete was reinforced with A252 mesh. The perimeter was then sprinkled with gravel to add a final touch, and the concrete was completed with a brushed finish to prevent it from becoming a slip hazard.

The final addition was the Armco barriers, used to protect the area from vehicles travelling around the site.

Conclusion

After just a week on site we were able to deliver our client exactly what they were looking for: a purpose built concrete base with the future requirements of their business in mind.

Once the specialist fridges have been installed, we will be returning to site to install a protective fence.



The 150m² area was excavated by our team on site, who then installed and compacted a crushed concrete sub base, which was subsequently covered with the poured concrete you can see at finish level.